

Extending the Government Press building at Bangalore.

No.	Items of work	Per	Rate	Quantity	Cost	Remarks
			Rs. a. p.		Rs. a. p.	
1	Earthwork, excavation and filling basement ...	C. yd.		724		
2	Concrete ...	C. ft.		5,407		
3	Stone in chunam, foundation ...	"		9,412		
4	Do basement ...	"		3,761		
5	Burnt brick in mortar ...	"		16,668		
6	Stone slabs, 6" thick ...	S. ft.		938		
7	Brick in mortar, archwork ...	C. ft.		1,448		
8	Teakwood, strong pannelled doors with brass locks, hinges, etc., complete.	S. ft.		400		
9	Teakwood windows, glazed and veneitioned shutters with iron bars, etc., complete.	"		336		
10	Teakwood windows pannelled and glazed shutters with iron bars, etc., complete.	"		160		
11	Teakwood semi-circular fanlights over doors and windows with glazed swing shutters.	"		236		
12	Chunam plastering ...	Sq.		231'40		
13	Pointing basement with mortar ...	"		17'36		
14	Rolled steel girders and joists with painting, etc., complete.	Cwt.		314'71		
15	Teakwood work with wood oiling, etc., complete.	C. ft.		81'0		
16	Terrace, complete ...	Sq.		9'27		
17	Roofing with jack arches ...	"		43'92		
18	Flooring with clay tiles over 3" concrete and cement pointing.	"		82'03		
19	Flooring with Ouddappah slabs over 3" concrete and cement pointing.	"		3'16		
20	Cornice work, thick ...	R. ft.		404		
21	Do thin or light ...	"		274		
22	Whitewashing ...	Sq.		174'0		
23	Colorwashing ...	"		57'89		
24	String course ...	R. ft.		104		
25	Cast iron down ware pipes, etc. ...	L. S.		...		
26	Drainage around the building ...	"		...		
27	Clearing site... ...	"		...		
28	Painting doors, etc ...	Sq.		27'12		
29	Iron gate ...	L. S.		...		
30	Brick in mortar coping with glass pieces ...	R. ft.		160		
31	Do parapet in front ...	"		166		
32	Do do in rear ...	"		230		

J. E. A. D'CRUZ,
Executive Engineer.

TUMKUR DIVISION.

Dated 3rd—4th March 1913.

The attention of the public is invited to Notification dated 4th March 1913, published in the *Mysore Gazette* calling for tenders for improving the Nandihalli tank, Regd. No. 163 and excavating a feeder channel therefrom to Maidala Amanikere Regd. No. 155, Tumkur Taluk.

C. VIJAYARANGAM NAIDU,
Officiating Executive Engineer.